



CA-Plex Automatic Control

The control of Plex air handling units is performed with an integrated CA-Plex automatic control system.

- Factory installed.
- Plug-and-play installation.
- Hand-held or wall-mounted LCD display control panel.
- Energy efficient operation all year around.
- The control system can be connected to BMS via MODBUS.
- Communication with external units (chiller, heat-pump).

